Let us help you Stretch your fencing dollars

Your Area Dealer
AB Custom Fencing
250-996-8640
www.abcustomfencing.com
Your Animal Management Systems Specialist

GALLAGHER POWER FENCING

GALLAGHER POWER FENCING-WOOD POSTS

Offset Brackets on Existing Fence

- Power Wire
- 7 in Pigtail Offset (15m spacing)
- Superstrain insulators
- Permanent Fence Tightener

$0.31 per/m ($0.09 per/ft) - 1 wire

Wood Post Fence

- Line posts 7' x 4-5" (20m spacing)
- Wood post insulators
- Anchor posts 8' x 5-6"
- Superstrain insulators
- Power Wire (HT) Class 3
- Tension Spring
- Inline Permanent wire tighteners
- Long Bungy gate (1)
- XL undergate and conduit
- Cut out switch & L style joint clamps

$0.77 per/m ($0.23 per/ft) – 1 wire
$1.03 per/m ($0.31 per/ft) – 2 wire
$1.25 per/m ($0.38 per/ft) – 3 wire

- Rail 10' x 4-5" H brace kit
- Long Bungy gate (2)

$1.61 per/m ($0.49 per/ft) – 4 wire

- 3 wires +, 2 wires –

$1.83 per/m ($0.55 per/ft) – 5 wire

Estimate Installation Costs at 1.5 x of material

Traditional Barbed Wire Fencing

- Wood line posts 7'- 4-5", 5m spacing
- 2 wire twist droppers per panel
- Wood H bracing MOT standards
- 12 gauge Standard barb wire
- 1 x wire stick gate with handle

$2.95 per/m ($0.89 per/ft) – 4 wire
$3.18 per/m ($0.96 per/ft) – 5 wire

Estimate Installation Costs at 1.5 to 2 x of material

GALLAGHER POWER FENCING-PORTABLE

- Medium geared reel with 400m turbo wire.
- Single reel connector
- Pigtail Treadin post (10m spacing)

$0.89 per/m ($0.27 per/ft) - 1 wire

- Large geared reel with 800m turbo wire.
- Single reel connector
- Pigtail Treadin post (10m spacing)

$0.78 per/m ($0.24 per/ft) – 1 wire

- 3 x Medium geared reel with 400m turbo wire.
- Reel Stand
- Multi reel connector
- Plastic Multiwire Treadin post (8m spacing)

$2.27 per/m ($0.67 per/ft) – 3 wire

- Medium Reel with 500m Polywire *.
- Single reel connector
- Pigtail Treadin post (10m spacing)

$0.68 per/m ($0.21 per/ft) – 1 wire

*note 500m is maximum usable range dew to resistance

GALLAGHER POWER FENCING- With PowerFlex Posts

- PowerFlex Posts (15m spacing)
- Dropper Clips
- Anchor posts 8' x 5-6" with deadman or auger anchor
- Superstrain insulators
- Power Wire (HT) Class 3
- Tension Spring
- Inline Permanent wire tighteners
- Long Bungy gate (1)
- XL undergate and conduit
- Cut out switch & L style joint clamps

$0.81 per/m ($0.25 per/ft) – 1 wire
$1.05 per/m ($0.32 per/ft) – 2 wire
$1.32 per/m ($0.40 per/ft) – 3 wire

Estimate Installation Costs at 1 x of material

Note: This is NOT a price quotation. It is an approximate calculation for comparison purposes. It does not include price of energizer, or the cost of labour to construct fence. Actual fence costs will vary depending on quantity of material used, price of materials, and cost of labour. Comparison is based on a 1000m straight section of fence with one 30ft gate way and includes all recommend material necessary to construct a high quality fence. Installation estimate costs are based on a general average determined from our installation production and hourly rate. They may vary due to terrain, complexity of project, time of year, travel, labour, and equipment requirements. Energizer costs can very from $0.05-$0.75 per/m depending on power source available and amount of fence the energizer is servicing. AB Custom Fencing Feb. 2009